

Balance kubatur

Staničení	Vzdálenost	Nákladiště			
		výkop		násyp	
		m ²	m ³	m ²	m ³
0.000		10.91		0	
	14.23		172.54		0.00
14.230		13.34		0	
	24.29		548.95		0.00
38.520		31.86		0	
	24.27		824.09		0.00
62.790		36.05		0	
	24.26		885.25		0.00
87.050		36.93		0	
	24.15		843.20		0.00
111.200		32.9		0	
	23.87		719.56		0.00
135.070		27.39		0	
	24.18		731.45		0.00
159.250		33.11		0	
	19.34		427.99		0.00
178.590		11.15		0	
	6.47		56.68		0.00
185.060		6.37		0	
	14.94		61.70		0.00
200.000		1.89		0	
	10.59		20.65		0.00
210.590		2.01		0	
	7.41		15.60		0.00
218.000		2.2		0	
			5307.65 m ³		0.0 m ³

Odpočet:

vybourání bet. zdi (nakl.rampy) 92 m³Výkop celkem: 5215.65 m³

Odvoz na skládku:

dosyp krajnic 68.45 m³Odvoz celkem: 5147.20 m³sanace podloží (mísení na místě) 1904 m³výkop rýh (vsakovací rýha) 435 m³