



Railway Infrastructure Administration, state organization
Construction administration East
Nerudova 1
772 58 Olomouc

Subject: Transport Terminal Uherský Brod – II. stage - part RIA
Additional information – Amendment no. 3

Query no. 7:

SO 23-17-01 Railway track superstructure

In the budget specification, there is the item no. 9 titled “Railway track equipment” with total length of 482 m. Not clear as specified the scope of works and supplies, not available in more detail even within the Technical report. Will the contracting authority send any more detailed specification and localization of works and supplies for the railway track equipment?

Reply:

All the necessary railway track equipment forms part of railway superstructure object, which shall include signals marking the exact location on the track as per RIA regulation no. D1:
Signal “End of platform” (white rectangular board with a black edge, built on the longer side) indicating the location, in front of which shall stop the first rolling stock used for passenger transport of the train, which shall within the designated location perform the loading and unloading of the passengers. In case of the trains shorter than the total length of the platform, the train drivers must stop the train so that the passenger vehicle was as close as possible to the person staying on the platform the closest to the “end of platform” signal and all the passenger vehicles were at the platform.

Query no. 8:

SO 23-17-01 Railway track superstructure

In the budge specification, there is also the item no. 8 Track geometry performance (project, measurements, signals) with total length of 482 m. Not clear as specified the total number and type of the signals, not available even within the technical report. Will the contracting authority send any more detailed specification for the signals?

Reply:

The item includes all the activities associated with the provision of special track alignment during the construction phase as well as after the construction. With regard to the nature and extent of the construction works, the item was summarized into the total length of the track modification. The



Správa železniční dopravní cesty

Railway Infrastructure Administration, state organization
Construction administration East
Nerudova 1
772 58 Olomouc

contractor shall perform pricing of the item based on his own professional experience and common practice with the construction project of similar nature.

Query no. 9:

SO 23-17-01 Railway track superstructure

In the technical report, there is a reference to landscaping of pedestrian trails and other surrounding areas using the chippings. The works and supplies are not reflected in the current budget specification. Will the contracting authority amend the budget with the works?

Reply:

The material used for the railway track trail shall conform to the requirements of regulation RIA no. S3 provision no.16 part X. With regard to the extent of the construction works, the total item of gravel bed was supplemented also with marginal portion of item titled "landscaping of embedded gravel bed". In order to avoid any doubt, the chief architect provides the total surface area of embedded gravel bed landscaping, with total area of 877 m².

.....
Dr. Ing. Václav John
ředitel organizační jednotky
Stavební správa východ
na základě pověření
Správa železniční dopravní cesty,
státní organizace